

SCOPE OF WORK — Bathroom Remodel

Project: Johnson Master Bathroom Renovation

Location: 123 Oak Street, Wilmington NC 28401

Client: Mark Johnson

Date: May 10, 2026

Prepared by: ABC Construction LLC

1. DEMOLITION

- Remove existing shower enclosure, shower pan, and all wall tile.
- Demolish existing vanity, countertop, and mirror.
- Remove existing toilet and disconnect plumbing.
- Strip all flooring down to subfloor. Haul away all debris.

2. FRAMING & STRUCTURAL

- Frame new shower alcove 48 inches x 36 inches.
- Install blocking for grab bars and shower glass.
- Verify subfloor integrity; replace any water-damaged sections.

3. PLUMBING

- Relocate shower drain to center of new shower footprint.
- Install new PEX supply lines for shower valve and vanity.
- Install new toilet flange and supply line.
- Connect double-vanity with two undermount sinks.

4. ELECTRICAL

- Install 6 recessed LED can lights on dimmer switch.
- Install 2 GFCI outlets above vanity area.
- Wire and install new exhaust fan with humidity sensor.
- All electrical work per NEC code on dedicated 20-amp circuit.

5. TILE WORK

- Install cement board substrate on all shower walls.
- Apply waterproof membrane (Schluter DITRA) in shower and floor.
- Install porcelain tile 12x24 floor-to-ceiling in shower area.
- Install porcelain tile 12x24 on bathroom floor.
- Room dimensions: 10 ft x 12 ft, ceiling height 9 ft.

6. FIXTURES & FINISHES

- Install 60-inch double vanity (white shaker style) with quartz countertop.
- Install frameless glass shower door 48x72.
- Install new elongated comfort-height toilet.
- Install all trim, accessories, and towel bars.

7. PAINTING

- Prime all new drywall surfaces.
- Apply 2 coats interior latex paint (semi-gloss for bathroom).
- Paint color to be selected by homeowner.

8. NOTES & EXCLUSIONS

- Homeowner responsible for fixture selections not listed above.
- Price does not include heated floor system. Add \$1,200 if desired.
- All work subject to building, plumbing, and electrical permits.
- Estimated timeline: 3 weeks from permit approval.