

CONSTRUCTION SCOPE OF WORK

Commercial Office Buildout — Suite 200

Project: Riverside Properties LLC — Office Renovation

Location: 456 Market Street, Suite 200, Raleigh NC 27601

Total Area: 2,400 sq ft

Date: May 5, 2026

PHASE 1: DEMOLITION & SITE PREP

- Demolish all existing partition walls and ceiling grid.
- Remove existing carpet and VCT flooring throughout.
- Remove all existing light fixtures and electrical devices.
- Cap and seal all existing plumbing lines at walls.

PHASE 2: FRAMING & DRYWALL

- Frame 6 new private offices using metal studs (3-5/8 inch).
- Frame 1 large conference room (20 ft x 16 ft).
- Frame break room with kitchenette area.
- Install 5/8 inch drywall on all new walls, tape, mud, and sand.
- Install new suspended acoustical ceiling grid throughout.

PHASE 3: ELECTRICAL

- Install new 200-amp electrical panel for suite.
- Wire all offices with duplex outlets per code (every 6 feet).
- Install dedicated 20-amp circuits for break room appliances.
- Install LED 2x4 troffer lights in ceiling grid (48 total).
- Install network conduit runs to all offices for data/phone.
- Install emergency exit lighting per fire code.

PHASE 4: PLUMBING

- Install break room sink with hot and cold supply lines.
- Connect dishwasher supply and drain in break room.
- Install drinking fountain in common hallway.

PHASE 5: HVAC

- Install 2 new mini split HVAC systems for independent zone control.
- Extend existing duct work to new office layout.
- Install thermostat in each office zone.

PHASE 6: FLOORING

- Install luxury vinyl plank flooring throughout (2,400 sq ft).
- Install rubber transition strips at all doorways.

PHASE 7: PAINTING & FINISHES

- Prime and paint all new drywall — 2 coats eggshell finish.
- Install commercial-grade door hardware on all offices.
- Install window blinds on all exterior windows (8 total).
- Install ADA-compliant signage on all rooms.

PHASE 8: FIRE & SAFETY

- Install fire sprinkler heads per NFPA code in all new rooms.
- Install smoke detectors and carbon monoxide detectors.
- Install fire extinguisher cabinets (2 locations).
- All work to meet ADA accessibility requirements.

BUDGET ESTIMATE

Total estimated material cost: \$18,400

Total estimated labor cost: \$24,000

Permits and fees: \$1,200

Contingency (10%): \$4,360

TOTAL PROJECT ESTIMATE: \$47,960