

KITCHEN RENOVATION — SCOPE OF WORK

Project: Williams Kitchen Remodel

Location: 789 Pine Drive, Durham NC 27707

Client: Sarah Williams

Kitchen Dimensions: 14 ft x 18 ft, ceiling height 10 ft

Total Kitchen Area: 252 sq ft

1. DEMOLITION

- Remove all existing cabinets (upper and lower).
- Remove existing countertops and backsplash tile.
- Demolish non-load-bearing wall between kitchen and dining room.
- Remove existing vinyl flooring down to subfloor.
- Disconnect and remove existing appliances (range, dishwasher, disposal).

2. STRUCTURAL

- Install LVL beam to replace load-bearing wall (per engineer's specs).
- Frame new island peninsula (4 ft x 8 ft).
- Repair and level subfloor as needed.

3. PLUMBING

- Relocate kitchen sink to new island location.
- Install new garbage disposal.
- Run gas line to new range location.
- Install dishwasher supply and drain connections.
- Install pot-filler faucet at range wall.

4. ELECTRICAL

- Install 6 recessed LED can lights over work areas.
- Install 3 pendant lights over island.
- Install under-cabinet LED strip lighting.
- Install GFCI outlets every 4 feet along countertops (per code).
- Install dedicated circuits for range, refrigerator, dishwasher, disposal.
- Upgrade electrical panel to accommodate new load.

5. CABINETRY & COUNTERTOPS

- Install custom shaker-style cabinets (white) — 14 lower, 10 upper.
- Install quartz countertops (Calacatta Gold) on perimeter and island.

6. TILE & BACKSPLASH

- Install ceramic subway tile backsplash (white 3x6).
- Backsplash from countertop to upper cabinets on all walls.

7. FLOORING

- Install luxury vinyl plank flooring throughout kitchen and dining area.
- Total flooring area approximately 400 sq ft.

8. PAINTING

- Prime and paint all new drywall and patched areas.
- Apply 2 coats Benjamin Moore Chantilly Lace (OC-65) semi-gloss.